AURUM PROJECT CONTROLS

Sample Bill of Quantities

Work-item excerpt from the supplied BOQ. Client details and summary sheets are excluded. Layout adapted for this preview.

SAMPLE — FOR ILLUSTRATION ONLY

Rates are illustrative source figures in NGN, not a current quotation. Quantities are unfilled in the source. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (NGN)	Amount (NGN)
SUBSTRUCTURES (All Provisional)					
A	Excavate to reduce level	—	CM	500	—
B	Excavate trench foundations	—	CM	500	—
C	Excavate column bases	—	CM	500	—
D	Return fill and ram excavated material around walls and foundations	—	CM	350	—
E	Load up excavated material and cart away from site.	—	CM	450	—
F	Approved laterite filling in making up levels well rammed and consolidated in 200mm layers	—	CM	2,500	—
G	Heavy duty polythene sheeting well lapped and laying over filling	—	SM	250	—
	Plain insitu concrete (1:8) blinding bed				
H	40mm Blinding bed	—	CM	15,000	—
J	Plain insitu concrete (Grade 20) in trench foundations	—	CM	28,000	—
	In-situ reinforced concrete (Grade 20)				
K	Column bases	—	CM	30,000	—
L	Column	—	CM	30,000	—
M	Ground floor slab	—	CM	30,000	—

SAMPLE

Preview only. Final BOQs are prepared for the agreed project scope.