AURUM

PROJECT CONTROLS

SAMPLE PROJECT DOCUMENT

5 Unit 2 Bedroom Building BOQ

Bill of Quantities

SAMPLE

DOCUMENT REF. AUR-SAMPLE-BOQ-002 | REVISION 01

Prepared by Aurum Project Controls

Detailed bills, collections, cost summary and quantity basis.

Five detached two-storey dwellings. Modelled quantities and supplied rates.

Illustrative sample only; not issued for tender or construction.

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	SAMPLE FIVE-DWELLING DEVELOPMENT - MODELLED QUANTITIES; SUPPLIED GBP RATES				
	BILL Nr 2 - 5 UNITS - 2BEDROOM BUILDING				
	SUBSTRUCTURES (All Provisional)				
A	Excavate to reduce level	60	CM	500.00	30,000.00
B	Excavate trench foundations	144	CM	500.00	72,000.00
C	Excavate column bases	69.12	CM	500.00	34,560.00
D	Return fill and ram excavated material around walls and foundations	125.86	CM	350.00	44,051.00
E	Load up excavated material and cart away from site.	147.26	CM	450.00	66,267.00
F	Approved laterite filling in making up levels well rammed and consolidated in 200mm layers	120	CM	2,500.00	300,000.00
G	Heavy duty polythene sheeting well lapped and laying over filling	400	SM	250.00	100,000.00
	Plain insitu concrete (1:8) blinding bed				
H	40mm Blinding bed	8.06	CM	15,000.00	120,900.00
J	Plain insitu concrete (Grade 20) in trench foundations	36	CM	28,000.00	1,008,000.00
	In-situ reinforced concrete (Grade 20)				
K	Column bases	14	CM	30,000.00	420,000.00
L	Column	1.38	CM	30,000.00	41,400.00
M	Ground floor slab	60	CM	30,000.00	1,800,000.00
	PAGE 2/1 TO COLLECTION				4,037,178.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	Formwork				
A	Sides of column base	56	SM	1,500.00	84,000.00
B	Sides of column and beds	50.92	SM	1,500.00	76,380.00
	Reinforcement quantities are provisional allowances; see Quantity basis. **High tensile steel reinforcement (design stress** **412N/mm2) in bases and columns**				
C	12mm Diameter reinforcement	691.89	Kg	260.00	179,891.40
D	16mm Diameter reinforcement	691.89	Kg	260.00	179,891.40
E	20mm Diameter reinforcement	576.58	Kg	260.00	149,910.80
F	10mm Diamter links	345.95	Kg	260.00	89,947.00
G	Steel mesh reinforcement ref A142 in bed well lapped (measured nett)	400	SM	12,500.00	5,000,000.00
H	230mm Hollow blockwork in cement mortar and filled solid with concrete (Grade 15)	156	SM	18,000.00	2,808,000.00
J	Provide a Sum for additional foundations to be expended as directed	1	sum	750,000.00	750,000.00
	PAGE 2/2 TO COLLECTION				9,318,020.60

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	SUBSTRUCTURE				
	Collection				
	Page 2/1				4,037,178.00
	Page 2/2				9,318,020.60
	SUBSTRUCTURE PAGE 2/3 TO SUMMARY				13,355,198.60

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	STRUCTURE				
	Reinforced in-situ concrete (Grade 20)				
A	Columns	12.7	CM	30,000.00	381,000.00
B	Floor beams	24.84	CM	30,000.00	745,200.00
C	Roof beams	16.56	CM	30,000.00	496,800.00
D	Staircase	3.3	CM	30,000.00	99,000.00
E	Lintel	0	CM	30,000.00	0
F	Suspended floor slab	60	CM	30,000.00	1,800,000.00
	Formwork				
J	Sides of column	220.8	SM	1,500.00	331,200.00
K	Sides and soffit of floor beams	271.2	SM	1,500.00	406,800.00
L	Sides and soffit of roof beams	199.2	SM	1,500.00	298,800.00
M	Sides and soffit of lintel	0	SM	1,500.00	0
N	Soffit of suspended slab	400	SM	1,500.00	600,000.00
O	Sides and sloping soffit of staircase	28	SM	1,500.00	42,000.00
	PAGE 2/4 TO COLLECTION				5,200,800.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	Reinforcement quantities are provisional allowances; see Quantity basis. **High tensile steel reinforcement (design stress** **412N/mm2) in columns beams and slabs**				
A	12mm Diameter reinforcement	6691.57	Kg	260.00	1,739,808.20
B	16mm Ditto	8922.1	Kg	260.00	2,319,746.00
C	10mm Diameter reinforcement	4461.05	Kg	260.00	1,159,873.00
D	10mm Diamter links	2230.52	Kg	260.00	579,935.20
	Precast concrete (Grade 20) cast in convenient lengths and bedded and jointed in cement mortar finished fair all round				
E	Window cill size 75 x 280mm wide weathered and throated	44.5	M	2,500.00	111,250.00
F	Lintel 230 x 150mm reinforced with and including four 12mm diameter bars and 8mm links at 200mm centres	90	M	3,500.00	315,000.00
	PAGE 2/5 TO COLLECTION				6,225,612.40

SAMPLE

SAMPLE • FOR ILLUSTRATION ONLY

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	STRUCTURE COLLECTION				
	PAGE 2/4				5,200,800.00
	PAGE 2/5				6,225,612.40
	STRUCTURE PAGE 2/6 TO SUMMARY				11,426,412.40

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	ROOFS **0.7mm Corrugated aluminium roof sheeting (colour coated on one side) and accessories with corrugation side laps and fixing with aluminium hook bolts and nylon washers and caps and seam bolts and washers and well lapped in accordance with manufacturer's instructions (measured nett)**				
A	Roof sheeting to slope	571.58	SM	3,800.00	2,172,004.00
	0.7mm Flat aluminium accessories with 100mm laps **fixed with seam bolts and plugged and screwed**				
B	Ridge piece 600mm girth	55	M	2,280.00	125,400.00
C	Eaves angle piece 300mm girth	110	M	1,140.00	125,400.00
D	Flashing 600mm girth once bent	0	M	2,280.00	0
E	Capping 450mmm girth twice bent	103.92	M	1,710.00	177,703.20
	Approved treated sawn hardwood members framed and nailed together as detailed				
F	75 x 100mm Wall plate	180	M	250.00	45,000.00
G	50 x 150mm Rafters	1039.23	M	300.00	311,769.00
H	50 x 150mm Tie beams	900	M	300.00	270,000.00
J	50 x 150mm Struts	400	M	200.00	80,000.00
K	50 x 75mm Purlins	550	M	250.00	137,500.00
	50 x 50mm Noggins	1416.67	M	175.00	247,917.25
	PAGE 2/7 TO COLLECTION				3,692,693.45

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
A	18 x 350mm Wrought hardwood fascia well seasoned and treated and primed and painted two coats gloss	213.92	M	350.00	74,872.00
B	Pergola size 3000 x 1500mm on plan comprising 50 x 100mm well seasoned and treated wrought hardwood members spaced 150mm apart both ways and well framed together and screwed to and including steel brackets plugged and screwed to wall and primed and painted two coats gloss	5	Nr	30,000.00	150,000.00
	PAGE 2/8 TO COLLECTION				224,872.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	ROOFS (Contd.)				
	Collection				
	Page 2/7				3,692,693.45
	Page 2/8				224,872.00
	ROOFS PAGE 2/9 TO SUMMARY				3,917,565.45

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	EXTERNAL CLADDING & AND INTERNAL PARTITIONS				
	Hollow blockwalling in cement mortar				
A	230mm Wall	980.11	SM	3,500.00	3,430,385.00
B	150mm Ditto	1119.68	SM	3,000.00	3,359,040.00
	Powder coated aluminium doors and windows complete with tinted glass and insect screens and all accessories screwed to and including metal subframes built into blockwork and pointing all round in silicone mastic				
C	Projected window size 900 x 900mm high overall	5	Nr	35,000.00	175,000.00
D	Projected window size 900 x 1200mm high overall	10	Nr	40,000.00	400,000.00
E	Sliding window size 2300 x 1200mm high overall	5	Nr	86,400.00	432,000.00
F	Casement size 1200 x 1200mm high	10	Nr	90,000.00	900,000.00
G	Casement size 1500 x 1200mm high	5	Nr	100,000.00	500,000.00
	PAGE 2/10 TO COLLECTION				9,196,425.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
A	Proprietary metal security entrance door size 1200 x 2175mm overall complete with spy hole frame and all ironmongery and built into wall	5	Nr	150,000.00	750,000.00
B	Proprietary metal security entrance door size 900 x 2175mm overall complete with spy hole frame and all ironmongery and built into wall	5	Nr	100,000.00	500,000.00
C	Garage door size 2500 x 2000mm high comprising galvanised sheet metal roller shutters complete with all accessories	5	Nr	150,000.00	750,000.00
	Hardwood solid core flush door covered both sides with veneered plywood and hung on and including 75 x 230mm hardwood door lining rebated and covered both edges with 25 x 50mm splayed architrave and including hinges locks and other ironmongery				
D	Door and lining size 900 x2100mm high overall	30	Nr	65,000.00	1,950,000.00
E	Ditto size 750 x 2100mm high overall	15	Nr	65,000.00	975,000.00
F	Prepare and apply polish to approval on hardwood doors and lining	160.65	SM	650.00	104,422.50
	PAGE 2/11 TO COLLECTION				5,029,422.50

SAMPLE

SAMPLE • FOR ILLUSTRATION ONLY

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	EXTERNAL CLADDING & INTERNAL PARTITIONS				
	Collection				
	Page 2/10				9,196,425.00
	Page 2/11				5,029,422.50
	EXTERNAL CLADDING & INTERNAL PARTITIONS				
	PAGE 2/12 TO SUMMARY				14,225,847.50

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	FITTINGS				
A	Provide a Sum for Staircase baluatrades and handrails to balconies to be expended as directed	1	sum	5,000,000.00	5,000,000.00
B	Provide a Sum for Kitchen Cabinets to be expended as directed	1	sum	1,500,000.00	1,500,000.00
C	Provide a Sum for Wardrobes, Walk-in Closets and Stores to be expended as directed	1	sum	1,500,000.00	1,500,000.00
D	Provide a Sum for burglar proofing to be expended as directed	1	sum	900,000.00	900,000.00
E	Provide a Sum for Duct cover to be expended as directed	1	sum	500,000.00	500,000.00
	FITTINGS PAGE 2/ 13 TO SUMMARY				9,400,000.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	FINISHES				
	Wall Finishes				
	Smooth internal rendering including narrow widths				
A	Walls	3219.46	SM	2,500.00	8,048,650.00
B	Concrete soffits	400	SM	3,500.00	1,400,000.00
	POP (gypsum plaster) screeding				
C	Rendered walls	2969.46	SM	600.00	1,781,676.00
D	Rendered soffits	400	SM	650.00	260,000.00
	Prepare and apply primer and one finishing coats of Dulux high quality emulsion				
E	POP and rendered walls	2969.46	SM	1,100.00	3,266,406.00
F	POP and rendered concrete soffits	400	SM	500.00	200,000.00
G	Smooth external rendering on walls including narrow widths	980.11	SM	2,500.00	2,450,275.00
H	Prepare and apply high quality Texcote paint on rendered walls externally	980.11	SM	1,100.00	1,078,121.00
J	200 x 200 x 4mm Ceramic wall tiles PC £2,000/m2 bedded and jointed in cement mortar and pointed in coloured cement to match including narrow widths	250	SM	3,500.00	875,000.00
	PAGE 2/14 TO COLLECTION				19,360,128.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	Floor Finishes **300 x 300 x 6mm Light grey vitrified ceramic floor tiles PC £3,000/m2 bedded and jointed in cement mortar and pointed in coloured cement to match including laying to approved pattern**				
A	To floors	600	SM	4,500.00	2,700,000.00
B	Skirting 100mm wide	550	M	500.00	275,000.00
	600 x 300 x 8mm Polished granite floor tiles PC £8000/m2 bedded and jointed in cement mortar and pointed in coloured cement to match including laying to approved pattern				
C	To floors	85	SM	7,900.00	671,500.00
D	Treads 250mm wide with non-slip grooves	88	M	1,975.00	173,800.00
E	Risers 150mm wide	88	M	1,185.00	104,280.00
F	Skirting 100mm wide	150	M	790.00	118,500.00
	Cement and sand (1:4) Beds and Backing				
G	50mm Paving finished with non-slip top surface	75	SM	25,000.00	1,875,000.00
H	44mm Screeded bed	685	SM	45,000.00	30,825,000.00
J	15mm Screeded backing	250	SM	9,500.00	2,375,000.00
	PAGE 2/15 TO COLLECTION				39,118,080.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	Ceiling Finishing				
A	12mm Plasterboard sheet nailed to hardwood nogggins (measured separately) spaced at 600mm centres both ways with joints masked in tape and finished in gypsum plaster smooth	400	SM	3,000.00	1,200,000.00
B	Moulded cornice in gypsum plaster at joint of ceiling and wall	600	M	1,500.00	900,000.00
C	Prepare prime and paint two coats emulsion on plaster soffits	400	SM	550.00	220,000.00
D	Approved PVC ceiling slats at eaves screwed to hardwood noggins (measured separately) spaced at 600mm centres	50	SM	7,800.00	390,000.00
	PAGE 2/16 TO COLLECTION				2,710,000.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	FINISHES **COLLECTION**				
	PAGE 2/14				19,360,128.00
	PAGE 2/15				39,118,080.00
	PAGE 2/16				2,710,000.00
	FINISHES PAGE 2/17 TO SUMMARY				61,188,208.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	SERVICES INSTALLATION				
	Electrical Installation				
A	Provide a Sum for Electrical Installation to be expended as directed	1	sum	8,000,000.00	8,000,000.00
	Mechanical Installation				
D	Provide a Sum for Plumbing Installation to be expended as directed	1	sum	5,000,000.00	5,000,000.00
	SERVICES INSTALLATIONS PAGE 2/18 TO SUMMARY				13,000,000.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	BILL Nr 2 - FIVE TWO-BEDROOM DWELLINGS				
	SUMMARY				
	SUBSTRUCTURES (page 2/3)				13,355,198.60
	STRUCTURE (page 2/6)				11,426,412.40
	ROOFS (page 2/9)				3,917,565.45
	EXTERNAL CLADDING & INT PARTITIONS(page 2/12)				14,225,847.50
	FITTINGS (page 2/13)				9,400,000.00
	FINISHES (page 2/17)				61,188,208.00
	SERVICES INSTALLATION (page 2/18)				13,000,000.00
	BILL Nr 2 - 5 UNITS 2 BEDROOM BUILDING				
	CARRIED TO MAIN SUMMARY				126,513,231.95

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	BILL Nr 5 - EXTERNAL WORKS (All Provisional)				
	SITE WORKS				
A	Clear site of all grass debris and other delecterious material and cart away from site (area of approximately 6200 sq metres)	1	sum	200,000.00	200,000.00
B	Approved laterite filling in making up levels on site	3900	CM	2,500.00	9,750,000.00
	Car Park and Walkways				
B	Approved sand filling in making up levels spread and levelled				
	and consolidated in 200mm layers with approved vibrating				
	machine (Provisional)	582	CM	2,000.00	1,164,000.00
C	80mm Precast concrete interlocking road paviors (approved design)				
	laid on and including 50mm sand bed to approved pattern	1940	SM	3,800.00	7,372,000.00
D	100 x 300mm Plain precast concrete (Grade20) half battered	378	M	2,500.00	945,000.00
	kerb cast in 600mm lengths bedded jointed and pointed in **cement mortar (1:3) on and including 300 x 100mm concrete** **(Grade 20) foundation with haunching up one side and** **including all necessary excavation forwork and disposal**				
E	Ditto curved	55	M	2,600.00	143,000.00
	External Works Page 5/1 to Collection				19,574,000.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	Soft Landscaping				
A	Approved vegetable soil or black humus topsoil 150mm thick	921	SM	750.00	690,750.00
	free from stones weeds roots etc and spread and level and sprayed with ammonia nitrate or other approved fertiliser				
B	Plant cynodon dactylon (Bahama grass) or other approved carpet	921	SM	350.00	322,350.00
	grass at 150mm centres in all directions and well water until well established including replacing dead patches until the whole area is evenly covered with a healthy growth				
C	Provide a Sum for Planting shrubs and flowers to be expended as directed	1	sum	750,000.00	750,000.00
	Fencing				
D	Excavate trench and bases for foundations and disposal	310	CM	550.00	170,500.00
E	50mm Concrete (1:8) blinding bed under bases	138	SM	10,000.00	1,380,000.00
F	Plain in-situ concrete (grade 15) in trench foundations	47	CM	25,000.00	1,175,000.00
	In-situ reinforced concrete (Grade 20)				
G	Column bases	32	CM	30,000.00	960,000.00
H	Columns	27	CM	30,000.00	810,000.00
	Formwork				
J	Sides of bases	141	SM	1,250.00	176,250.00
K	Sides of columns	469	SM	1,250.00	586,250.00
	External Works Page 5/2 to Collection				7,021,100.00

SAMPLE

SAMPLE • FOR ILLUSTRATION ONLY

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	Fencing (contd)				
A	16mm Diameter high tensile reinforcement	3546	Kg	1,200.00	4,255,200.00
B	12mm Diameter high tensile reinforcement	2536	Kg	1,200.00	3,043,200.00
C	10mm Diameter mild steel links	1550	Kg	1,200.00	1,860,000.00
	Precast concrete (Grade 20) bedded in cement mortar and finished fair alll round				
D	50 x 300mm wide Saddle back coping throated both sides	299	M	2,500.00	747,500.00
E	Capping size 300 x300 x 100mm thick overall weathered and throated	170	Nr	5,000.00	850,000.00
F	230mm Hollow blockwalling in cement mortar	897	SM	3,500.00	3,139,500.00
G	Smooth rendering on walls externally in cement mortar as described	1420	SM	750.00	1,065,000.00
H	Prepare and prime and apply texcote or other approved textured	1420	SM	650.00	923,000.00
	paint on rendered walls				
J	Provide a sum for Wrought iron fence grilles to be expended as directed	1	sum	5,000,000.00	5,000,000.00
K	Provide a sum for Gates(2Nr) to be expended as directed	1	sum	1,000,000.00	1,000,000.00
L	Provide a Sum for Gate House to be expended as directed	1	sum	7,000,000.00	7,000,000.00
M	Provide a Sum for site drainage to be expended as directed	1	sum	5,000,000.00	5,000,000.00
N	Provide a Sum for soil drainage to be expended as directed	1	sum	20,000,000.00	20,000,000.00
	External Works Page 5/3 to Collection				53,883,400.00

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
A	Provide a Sum for Generator House to be expended as directed	1	sum	5,000,000.00	5,000,000.00
B	Provide a Sum for Borehole and Water Treatment to be expended as directed	1	sum	8,000,000.00	8,000,000.00
C	Provide a Sum for Water Storage and Distribution to be expended as directed	1	sum	10,000,000.00	10,000,000.00
D	Provide a Sum for Electricity Supply and Distribution to be expended as directed	1	sum	20,000,000.00	20,000,000.00
	External Works Page 5/4 to Collection				43,000,000.00

SAMPLE

SAMPLE • FOR ILLUSTRATION ONLY

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	BILL Nr 5 - EXTERNAL WORKS				
	Collection				
	Page 5/1				19,574,000.00
	Page 5/2				7,021,100.00
	Page 5/3				53,883,400.00
	Page 5/4				43,000,000.00
	BILL Nr 5 - EXTERNAL WORKS Page 5/5				123,478,500.00
	TO MAIN SUMMARY				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	SAMPLE FIVE-DWELLING DEVELOPMENT				
	MAIN SUMMARY				
	BILL Nr 1 - CONDITIONS OF CONTRACT,				
	PRELIMINARIES & SPECIFICATIONS				3,000,000.00
	BILL Nr 2 - FIVE TWO-BEDROOM DWELLINGS				126,513,231.95
	BILL Nr 5 - EXTERNAL WORKS				123,478,500.00
	Additional four-unit block A: excluded, supporting worksheet not supplied				0
	Additional four-unit block C: excluded, supporting worksheet not supplied				0
	Additional two-unit block D: excluded, supporting worksheet not supplied				0
	Duplicate external-works line: excluded to avoid counting the same bill twice				0
	CONTINGENCIES				
	Source contingency allowance retained				8,000,000.00
	SUBTOTAL BEFORE SOURCE VAT CALCULATION				260,991,731.95
	Source VAT calculation at 20% (sample arithmetic; tax treatment unverified)				52,198,346.39
	TOTAL CARRIED TO FORM OF TENDER				313,190,078.34
	Signature of Employer				
	Signature of Contractor				
	Completion period weeks				
	MS/1				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
	SAMPLE 2 - COMPLETION BASIS; READ WITH ALL BILL PAGES				
	This is a completed sample copy of the supplied template, not a measured client project. No drawings were supplied. Original source file remains unchanged.				
	Sample measurement model: five detached two-storey two-bedroom dwellings; each footprint 10 x 8 m, two 3 m storeys. Ground and upper gross areas are 400 m2 each. This model is a stated scope, not a survey.				
	Per dwelling: seven windows; two external doors; one garage shutter; six 900 mm and three 750 mm internal doors. Internal partitions total 80 m per dwelling, measured across both storeys.				
	Per dwelling net finished floors: ceramic 120 m2 + granite 17 m2 + garage 15 m2 = 152 m2; gross 160 m2 less 8 m2 wall/void allowance. Wall tiles: 50 m2 per dwelling.				
	Structural sizes and reinforcement quantities are provisional sample allowances, not structural design. Source mass allowances 150 kg/m3 (bases/stubs) and 190 kg/m3 (frame) are split by stated percentages; all require engineered schedules for a live project.				
	External-work quantities and all supplied lump sums are retained from the source; they were not measured against this model. Original rates and allowances remain GBP without conversion or market validation.				
	All priced amounts are displayed quantity x supplied rate, rounded to pence. Collections and summaries are recalculated. Zero means excluded/not applicable; alternative prices are zero because no alternative quotation was supplied.				
	Source unit key: CM = cubic metres (m3); SM = square metres (m2); M = linear metres; Kg = kilograms; Nr = number; sum = one complete provisional/lump-sum allowance.				
	Unsupported extra building bills from the source summary are explicitly excluded, rather than inventing entire missing buildings. The five-dwelling bill and external works are included once only.				
	The source 20% VAT arithmetic is retained for illustration only; applicability to an actual new-build project has not been established. Preliminaries and contingency are the original source allowances.				
	Measurement reference: RICS NRM guidance https://www.rics.org/profession-standards/rics-standards-and-guidance/sector-standards/construction-standards/nrm . No claim of full NRM compliance is made.				
	TO MAIN SUMMARY				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
1	Building row 9: 5 x 10 x 8 m footprint x 0.15 m reduced-level excavation	60	CM		
2	Building row 12: 240 m strip trenches x 0.60 m width x 1.00 m depth; separate from internal column pits	144	CM		
3	Building row 15: 40 separate internal column pits x 1.20 x 1.20 x 1.20 m	69.12	CM		
4	Building row 18: Trench/pit excavation less footing, bases, stubs and foundation blockwork volumes	125.86	CM		
5	Building row 21: Reduced-level + foundation excavation less return fill; all surplus removed	147.26	CM		
6	Building row 24: 400 m2 footprint x 0.30 m compacted fill	120	CM		
7	Building row 27: 400 m2 net footprint; laps included in the supplied rate	400	SM		
8	Building row 32: Strip/pit base areas x 0.04 m blinding thickness	8.06	CM		
9	Building row 35: 240 x 0.60 x 0.25 m strip footing	36	CM		
10	Building row 40: 40 x 1.00 x 1.00 x 0.35 m bases	14	CM		
11	Building row 43: 40 x 0.23 x 0.23 x 0.65 m column stubs	1.38	CM		
12	Building row 46: 400 m2 ground-floor slab x 0.15 m	60	CM		
13	Building row 55: 40 bases x four 1.00 m sides x 0.35 m depth	56	SM		
14	Building row 58: Column stub faces plus exposed slab perimeter edge	50.92	SM		
15	Building row 64: 30% of 150 kg/m3 provisional reinforcement allowance on bases and stubs	691.89	Kg		
	TO MAIN SUMMARY				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
16	Building row 67: 30% of the same provisional reinforcement allowance	691.89	Kg		
17	Building row 70: 25% of the same provisional reinforcement allowance	576.58	Kg		
18	Building row 73: 15% of the same provisional reinforcement allowance	345.95	Kg		
19	Building row 77: 400 m2 net ground-floor slab mesh; no lap area added	400	SM		
20	Building row 80: 240 m foundation wall length x 0.65 m height	156	SM		
21	Building row 161: 40 columns x 0.23 x 0.23 x 6.00 m above ground	12.7	CM		
22	Building row 164: 240 m floor-beam length x 0.23 x 0.45 m; separate sample beam/slab volumes	24.84	CM		
23	Building row 167: 240 m roof-beam length x 0.23 x 0.30 m	16.56	CM		
24	Building row 170: 5 stair waist slabs x 1.10 x 4.00 x 0.15 m; steps included in allowance	3.3	CM		
25	Building row 173: 0: lintels are priced with reinforcement under item F on source page 2/5; avoids duplicate pricing	0	CM		
26	Building row 176: 400 m2 upper-floor slab x 0.15 m	60	CM		
27	Building row 181: 40 columns x four 0.23 m sides x 6.00 m height	220.8	SM		
28	Building row 184: 240 m floor beams x two sides and soffit widths	271.2	SM		
29	Building row 187: 240 m roof beams x two sides and soffit widths	199.2	SM		
30	Building row 190: 0: precast lintel rate includes the complete item; no separate formwork	0	SM		
	TO MAIN SUMMARY				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
31	Building row 193: 400 m2 net suspended-floor soffit	400	SM		
32	Building row 196: 5 stairs: sloping soffit plus two waist edges	28	SM		
33	Building row 216: 30% of source 190 kg/m3 provisional reinforcement allowance; excludes precast lintels	6691.57	Kg		
34	Building row 219: 40% of the same provisional reinforcement allowance	8922.1	Kg		
35	Building row 222: 20% of the same provisional reinforcement allowance	4461.05	Kg		
36	Building row 226: 10% of the same provisional reinforcement allowance	2230.52	Kg		
37	Building row 231: Sum of window widths: seven scheduled windows per dwelling	44.5	M		
38	Building row 234: 18 m total precast lintel length per dwelling, including end bearings	90	M		
39	Building row 319: 5 separate 11 x 9 m roofs on plan, 30-degree slope; includes overhangs	571.58	SM		
40	Building row 324: 5 ridges x 11 m	55	M		
41	Building row 327: 5 roofs x two 11 m eaves	110	M		
42	Building row 330: 0: detached pitched roofs have no abutment flashing in this sample scope	0	M		
43	Building row 333: Four sloping verge edges per roof x 4.5/cos(30 degrees)	103.92	M		
44	Building row 338: Two 10 m wall plates plus two 8 m returns per dwelling	180	M		
45	Building row 341: 20 trusses per dwelling x two sloping rafters	1039.23	M		
	TO MAIN SUMMARY				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
46	Building row 344: 100 trusses x 9 m tie span	900	M		
47	Building row 347: 100 trusses x two 2 m struts	400	M		
48	Building row 350: Five purlin lines per roof slope x two slopes x 11 m	550	M		
49	Building row 353: 600 mm grid over 400 m2 upper ceiling, plus transverse noggins over 50 m2 eaves	1416.67	M		
50	Building row 365: Both eaves plus four sloping verges per roof	213.92	M		
51	Building row 368: One 3.00 x 1.50 m pergola per dwelling	5	Nr		
52	Building row 471: 180 m total external perimeter x 6 m height, less scheduled windows and external doors	980.11	SM		
53	Building row 474: 80 m internal partitions per dwelling x 3 m storey height, less internal door openings	1119.68	SM		
54	Building row 481: One 900 x 900 mm window per dwelling	5	Nr		
55	Building row 484: Two 900 x 1200 mm windows per dwelling	10	Nr		
56	Building row 487: One 2300 x 1200 mm window per dwelling	5	Nr		
57	Building row 490: Two 1200 x 1200 mm bedroom windows per dwelling	10	Nr		
58	Building row 493: One 1500 x 1200 mm window per dwelling	5	Nr		
59	Building row 520: One 1200 mm entrance door per dwelling	5	Nr		
60	Building row 523: One 900 mm external door per dwelling	5	Nr		
	TO MAIN SUMMARY				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
61	Building row 526: One garage shutter per dwelling; garage included in ground-floor footprint	5	Nr		
62	Building row 531: Six 900 mm internal doors per dwelling	30	Nr		
63	Building row 534: Three 750 mm internal doors per dwelling	15	Nr		
64	Building row 538: Both faces of 45 internal door leaves; lining finish included in rate	160.65	SM		
65	Building row 670: Internal face of external walls plus both faces of partitions, net of openings	3219.46	SM		
66	Building row 673: 400 m2 exposed lower-storey concrete soffits	400	SM		
67	Building row 679: Net internal wall rendering less 250 m2 tiled wall finish	2969.46	SM		
68	Building row 682: 400 m2 lower-storey soffit skim	400	SM		
69	Building row 687: Same net skimmed wall area; tiled areas excluded	2969.46	SM		
70	Building row 690: 400 m2 lower-storey painted concrete soffits	400	SM		
71	Building row 696: Net external wall area; one exterior face only	980.11	SM		
72	Building row 699: Same external rendered wall area	980.11	SM		
73	Building row 702: 50 m2 tiled kitchen/bathroom wall finishes per dwelling	250	SM		
74	Building row 720: 120 m2 ceramic floors per dwelling; total net floor area 152 m2 each	600	SM		
75	Building row 723: 110 m ceramic skirting per dwelling, excluding door gaps and granite zones	550	M		
	TO MAIN SUMMARY				

SAMPLE

Item	Description	Qty	Unit	Rate (£)	Amount (£)
76	Building row 728: 17 m2 granite circulation floors per dwelling; excludes ceramic and garage areas	85	SM		
77	Building row 731: 16 stair treads per dwelling x 1.10 m width	88	M		
78	Building row 734: 16 stair risers per dwelling x 1.10 m width	88	M		
79	Building row 737: 30 m granite skirting per dwelling, excluding ceramic zones	150	M		
80	Building row 744: 15 m2 garage floor finish per dwelling	75	SM		
81	Building row 747: Ceramic and granite floor areas: 120 + 17 m2 per dwelling	685	SM		
82	Building row 750: Backing to the 250 m2 wall tiling only	250	SM		
83	Building row 766: 400 m2 top-storey plasterboard ceiling	400	SM		
84	Building row 769: 120 m ceiling cornice per dwelling, after openings/untreated garage zones	600	M		
85	Building row 772: 400 m2 top-storey plasterboard ceiling painted	400	SM		
86	Building row 775: 10 m2 horizontal eaves soffit per dwelling	50	SM		
	TO MAIN SUMMARY				

SAMPLE