Bill 1 • Access

Refurbishment Building BOQ • SAMPLE • Historical GBP rates • Revision 03

Item	Description	Qty	Unit	Rate (£)	Amount (£)
1.01	Facade scaffolding; six-week hire	50	m²	51.31	2,565.50
1.02	Tower scaffolding; maximum 10m	2	nr	996.70	1,993.40
	Carried to summary				**4,558.90**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Bill 2 • Building fabric

Refurbishment Building BOQ • SAMPLE • Historical GBP rates • Revision 03

Item	Description	Qty	Unit	Rate (£)	Amount (£)
2.01	Render renewal with existing removal	200	m²	132.89	26,578.00
2.02	Mechanical repointing with existing removal	100	m²	57.14	5,714.00
2.03	15mm exterior plywood roof decking	50	m²	58.45	2,922.50
2.04	200mm mineral-wool roof insulation	25	m²	26.58	664.50
	Carried to summary				**35,879.00**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Bill 3 • Renewals

Refurbishment Building BOQ • SAMPLE • Historical GBP rates • Revision 03

Item	Description	Qty	Unit	Rate (£)	Amount (£)
3.01	Kitchen renewal; six units maximum	10	nr	7,020.84	70,208.40
3.02	WC renewal with hand basin	5	nr	1,888.20	9,441.00
	Carried to summary				**79,649.40**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Bill 4 • Electrical

Refurbishment Building BOQ • SAMPLE • Historical GBP rates • Revision 03

Item	Description	Qty	Unit	Rate (£)	Amount (£)
4.01	Additional double socket with box	10	nr	76.11	761.10
4.02	Additional light switch with box	10	nr	16.49	164.90
4.03	Additional smoke detector	20	nr	164.91	3,298.20
4.04	Occupied-property electrical testing after works	20	nr	164.91	3,298.20
	Carried to summary				**7,522.40**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Main summary

Refurbishment Building BOQ • SAMPLE • Historical GBP rates • Revision 03

Item	Description	Qty	Unit	Rate (£)	Amount (£)
1	Access				4,558.90
2	Building fabric				35,879.00
3	Renewals				79,649.40
4	Electrical				7,522.40
	Total of selected works				**127,609.70**

SAMPLE

Only the selected refurbishment work basket is totalled. Quantities are published evaluation quantities and rates are historical reference prices. VAT is not calculated. Confirm scope, measurements and current prices for a live project.