AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	RESIDENTIAL DEVELOPMENT AT GWARINPA FOR MR J R G						
	BILL Nr 2 - 5 UNITS - 2BEDROOM BUILDING						
	SUBSTRUCTURES (All Provisional)						
A	Excavate to reduce level		CM	500.00	0		
B	Excavate trench foundations		CM	500.00	0		
C	Excavate column bases		CM	500.00	0		
D	Return fill and ram excavated material around walls and foundations		CM	350.00	0		
E	Load up excavated material and cart away from site.		CM	450.00	0		0
F	Approved laterite filling in making up levels well rammed and consolidated in 200mm layers		CM	2,500.00	0		0
G	Heavy duty polythene sheeting well lapped and laying over filling		SM	250.00	0		
	Plain insitu concrete (1:8) blinding bed				0		0
H	40mm Blinding bed		CM	15,000.00	0		
J	Plain insitu concrete (Grade 20) in trench foundations		CM	28,000.00	0		
	In-situ reinforced concrete (Grade 20)				0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
K	Column bases		CM	30,000.00	0		0
L	Column		CM	30,000.00	0		
M	Ground floor slab		CM	30,000.00	0		0
	PAGE 2/1 TO COLLECTION				0		
	Formwork				0		
A	Sides of column base		SM	1,500.00	0		0
B	Sides of column and beds		SM	1,500.00	0		
	0				0		
	High tensile steel reinforcement (design stress				0		
	412N/mm2) in bases and columns				0		
	0				0		
C	12mm Diameter reinforcement		Kg	260.00	0		
D	16mm Diameter reinforcement		Kg	260.00	0		
E	20mm Diameter reinforcement		Kg	260.00	0		
F	10mm Diamter links		Kg	260.00	0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
G	Steel mesh reinforcement ref A142 in bed well lapped (measured nett)		SM	12,500.00	0		
H	230mm Hollow blockwork in cement mortar and filled solid with concrete (Grade 15)		SM	18,000.00	0		
J	Provide a Sum for additional foundations to be expended as directed				750,000.00		
	PAGE 2/2 TO COLLECTION				750,000.00		
	SUBSTRUCTURE **Collection**						
	Page 2/1				0		
	Page 2/2				750,000.00		
	SUBSTRUCTURE PAGE 2/3 TO SUMMARY				750,000.00		
	STRUCTURE						
	Reinforced in-situ concrete (Grade 20)				0		
A	Columns		CM	30,000.00	0		0
B	Floor beams		CM	30,000.00	0		0
C	Roof beams		CM	30,000.00	0		0

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
D	Staircase		CM	30,000.00	0		0
E	Lintel		CM	30,000.00	0		0
F	Suspended floor slab		CM	30,000.00	0		0
	Formwork				0		
J	Sides of column		SM	1,500.00	0		0
K	Sides and soffit of floor beams		SM	1,500.00	0		
L	Sides and soffit of roof beams		SM	1,500.00	0		
M	Sides and soffit of lintel		SM	1,500.00	0		
N	Soffit of suspended slab		SM	1,500.00	0		
O	Sides and sloping soffit of staircase		SM	1,500.00	0		0
	PAGE 2/4 TO COLLECTION				0		
	0						
	High tensile steel reinforcement (design stress				0		
	412N/mm2) in columns beams and slabs				0		
	0				0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
A	12mm Diameter reinforcement		Kg	260.00	0		
B	16mm Ditto		Kg	260.00	0		
C	10mm Diameter reinforcement		Kg	260.00	0		
D	10mm Diamter links		Kg	260.00	0		
	Precast concrete (Grade 20) cast in convenient lengths and bedded and jointed in cement mortar finished fair all round				0		
E	Window cill size 75 x 280mm wide weathered and throated		M	2,500.00	0		
F	Lintel 230 x 150mm reinforced with and including four 12mm diameter bars and 8mm links at 200mm centres		M	3,500.00	0		
	PAGE 2/5 TO COLLECTION				0		
	STRUCTURE COLLECTION						
	PAGE 2/4				0		Unavailable
	PAGE 2/5				0		Unavailable
	STRUCTURE PAGE 2/6 TO SUMMARY				0		Unavailable
	ROOFS						

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	0.7mm Corrugated aluminium roof sheeting (colour coated on one side) and accessories with corrugation side laps and fixing with aluminium hook bolts and nylon washers and caps and seam bolts and washers and well lapped in accordance with manufacturer's instructions (measured nett)						
A	Roof sheeting to slope		SM	3,800.00	0		0
	0.7mm Flat aluminium accessories with 100mm laps				0		
	fixed with seam bolts and plugged and screwed				0		
B	Ridge piece 600mm girth		M	2,280.00	0		0
C	Eaves angle piece 300mm girth		M	1,140.00	0		0
D	Flashing 600mm girth once bent		M	2,280.00	0		
E	Capping 450mmm girth twice bent		M	1,710.00	0		
	Approved treated sawn hardwood members framed and nailed together as detailed				0		
F	75 x 100mm Wall plate		M	250.00	0		
G	50 x 150mm Rafters		M	300.00	0		0
H	50 x 150mm Tie beams		M	300.00	0		0
J	50 x 150mm Struts		M	200.00	0		0

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
K	50 x 75mm Purlins		M	250.00	0		0
	50 x 50mm Noggins		M	175.00	0		
	PAGE 2/7 TO COLLECTION				0		
A	18 x 350mm Wrought hardwood fascia well seasoned and treated and primed and painted two coats gloss		M	350.00	0		
B	Pergola size 3000 x 1500mm on plan comprising 50 x 100mm well seasoned and treated wrought hardwood members spaced 150mm apart both ways and well framed together and screwed to and including steel brackets plugged and screwed to wall and primed and painted two coats gloss		Nr	30,000.00	0		
	PAGE 2/8 TO COLLECTION				0		
	ROOFS (Contd.)						
	Collection						
	Page 2/7				0		Unavailable
	Page 2/8				0		
							Unavailable
	ROOFS PAGE 2/9 TO SUMMARY				0		Unavailable
	EXTERNAL CLADDING & AND INTERNAL PARTITIONS						

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	Hollow blockwalling in cement mortar						
A	230mm Wall		SM	3,500.00	0		0
B	150mm Ditto		SM	3,000.00	0		
	Powder coated aluminium doors and windows complete with tinted glass and insect screens and all accessories screwed to and including metal subframes built into blockwork and pointing all round in silicone mastic				0		
C	Projected window size 900 x 900mm high overall		Nr	35,000.00	0		
D	Projected window size 900 x 1200mm high overall		Nr	40,000.00	0		
E	Sliding window size 2300 x 1200mm high overall		Nr	86,400.00	0		
F	Casement size 1200 x 1200mm high		Nr	90,000.00	0		
G	Casement size 1500 x 1200mm high		Nr	100,000.00	0		
	PAGE 2/10 TO COLLECTION				0		
A	Proprietary metal security entrance door size 1200 x 2175mm overall complete with spy hole frame and all ironmongery and built into wall		Nr	150,000.00	0		
B	Proprietary metal security entrance door size 900 x 2175mm overall complete with spy hole frame and all ironmongery and built into wall		Nr	100,000.00	0		
C	Garage door size 2500 x 2000mm high comprising galvanised sheet metal roller shutters complete with all accessories		Nr	150,000.00	0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	Hardwood solid core flush door covered both sides with veneered plywood and hung on and including 75 x 230mm hardwood door lining rebated and covered both edges with 25 x 50mm splayed architrave and including hinges locks and other ironmongery				0		
D	Door and lining size 900 x2100mm high overall		Nr	65,000.00	0		
E	Ditto size 750 x 2100mm high overall		Nr	65,000.00	0		
F	Prepare and apply polish to approval on hardwood doors and lining		SM	650.00	0		
	PAGE 2/11 TO COLLECTION				0		
	EXTERNAL CLADDING & INTERNAL PARTITIONS **0** **Collection**						
	Page 2/10				0		
	Page 2/11				0		
	EXTERNAL CLADDING & INTERNAL PARTITIONS						
	PAGE 2/12 TO SUMMARY				0		
	FITTINGS						

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
A	Provide a Sum for Staircase baluatrades and handrails to balconies to be expended as directed				5,000,000.00		
B	Provide a Sum for Kitchen Cabinets to be expended as directed				1,500,000.00		
C	Provide a Sum for Wardrobes, Walk-in Closets and Stores to be expended as directed				1,500,000.00		
D	Provide a Sum for burglar proofing to be expended as directed				900,000.00		
E	Provide a Sum for Duct cover to be expended as directed				500,000.00		
	FITTINGS PAGE 2/ 13 TO SUMMARY				9,400,000.00		
	FINISHES						
	Wall Finishes						
	Smooth internal rendering including narrow widths						
A	Walls		SM	2,500.00	0		0
B	Concrete soffits		SM	3,500.00	0		0
	POP (gypsum plaster) screeding				0		
C	Rendered walls		SM	600.00	0		
D	Rendered soffits		SM	650.00	0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	Prepare and apply primer and one finishing coats of Dulux high quality emulsion				0		
E	POP and rendered walls		SM	1,100.00	0		0
F	POP and rendered concrete soffits		SM	500.00	0		0
G	Smooth external rendering on walls including narrow widths		SM	2,500.00	0		
H	Prepare and apply high quality Texcote paint on rendered walls externally		SM	1,100.00	0		
J	200 x 200 x 4mm Ceramic wall tiles PC N2,000/m2 bedded and jointed in cement mortar and pointed in coloured cement to match including narrow widths		SM	3,500.00	0		0
	PAGE 2/14 TO COLLECTION				0		
	Floor Finishes				0		
	300 x 300 x 6mm Light grey vitrified ceramic floor tiles PC N3,000/m2 bedded and jointed in cement mortar and pointed in coloured cement to match including laying to approved pattern				0		
A	To floors		SM	4,500.00	0		0
B	Skirting 100mm wide		M	500.00	0		0
	600 x 300 x 8mm Polished granite floor tiles PC N8000/m2 bedded and jointed in cement mortar and pointed in coloured cement to match including laying to approved pattern				0		
C	To floors		SM	7,900.00	0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
D	Treads 250mm wide with non-slip grooves		M	1,975.00	0		
E	Risers 150mm wide		M	1,185.00	0		
F	Skirting 100mm wide		M	790.00	0		
	Cement and sand (1:4) Beds and Backing				0		
G	50mm Paving finished with non-slip top surface		SM	25,000.00	0		
H	44mm Screeded bed		SM	45,000.00	0		0
J	15mm Screeded backing		SM	9,500.00	0		0
	PAGE 2/15 TO COLLECTION				0		
	Ceiling Finishing						
A	12mm Plasterboard sheet nailed to hardwood nogggins (measured separately) spaced at 600mm centres both ways with joints masked in tape and finished in gypsum plaster smooth		SM	3,000.00	0		
B	Moulded cornice in gypsum plaster at joint of ceiling and wall		M	1,500.00	0		
C	Prepare prime and paint two coats emulsion on plaster soffits		SM	550.00	0		
D	Approved PVC ceiling slats at eaves screwed to hardwood noggins (measured separately) spaced at 600mm centres		SM	7,800.00	0		
	PAGE 2/16 TO COLLECTION				0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	FINISHES						
	COLLECTION						
	PAGE 2/14				0		Unavailable
	PAGE 2/15				0		Unavailable
	PAGE 2/16				0		
	FINISHES PAGE 2/17 TO SUMMARY				0		Unavailable
	SERVICES INSTALLATION						
	Electrical Installation						
A	Provide a Sum for Electrical Installation to be expended as directed				8,000,000.00		
	Mechanical Installation						
D	Provide a Sum for Plumbing Installation to be expended as directed				5,000,000.00		
	SERVICES INSTALLATIONS PAGE 2/18 TO SUMMARY				13,000,000.00		0
	BILL Nr 2 - 3 TERRACE UNITS						
	SUMMARY						
	SUBSTRUCTURES (page 2/3)				750,000.00		Unavailable

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | 5 units 2 bedroom building

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	STRUCTURE (page 2/6)				0		Unavailable
	ROOFS (page 2/9)				0		Unavailable
	EXTERNAL CLADDING & INT PARTITIONS(page 2/12)				0		Unavailable
	FITTINGS (page 2/13)				9,400,000.00		Unavailable
	FINISHES (page 2/17)				0		0
	SERVICES INSTALLATION (page 2/18)				13,000,000.00		
	BILL Nr 2 - 5 UNITS 2 BEDROOM BUILDING						
	CARRIED TO MAIN SUMMARY				23,150,000.00		
							Unavailable

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | Ext wrks priced

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	BILL Nr 5 - EXTERNAL WORKS (All Provisional)						
	SITE WORKS						
A	Clear site of all grass debris and other delecterious material and cart away from site (area of approximately 6200 sq metres)				200,000.00		
B	Approved laterite filling in making up levels on site	3900	CM	2,500.00	9,750,000.00		
	Car Park and Walkways				0		
B	Approved sand filling in making up levels spread and levelled				0		
	and consolidated in 200mm layers with approved vibrating				0		
	machine (Provisional)	582	CM	2,000.00	1,164,000.00		
C	80mm Precast concrete interlocking road paviors (approved design)				0		
	laid on and including 50mm sand bed to approved pattern	1940	SM	3,800.00	7,372,000.00		
D	100 x 300mm Plain precast concrete (Grade20) half battered	378	M	2,500.00	945,000.00		
	kerb cast in 600mm lengths bedded jointed and pointed in				0		
	cement mortar (1:3) on and including 300 x 100mm concrete				0		
	(Grade 20) foundation with haunching up one side and				0		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | Ext wrks priced

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	including all necessary excavation forwork and disposal				0		
E	Ditto curved	55	M	2,600.00	143,000.00		
	External Works Page 5/1 to Collection				19,574,000.00		
	Soft Landscaping						
A	Approved vegetable soil or black humus topsoil 150mm thick	921	SM	750.00	690,750.00		
	free from stones weeds roots etc and spread and level and				0		
	sprayed with ammonia nitrate or other approved fertiliser				0		
B	Plant cynodon dactylon (Bahama grass) or other approved carpet	921	SM	350.00	322,350.00		
	grass at 150mm centres in all directions and well water until				0		
	well established including replacing dead patches until the				0		
	whole area is evenly covered with a healthy growth				0		
C	Provide a Sum for Planting shrubs and flowers to be expended as directed				750,000.00		
	Fencing				0		
D	Excavate trench and bases for foundations and disposal	310	CM	550.00	170,500.00		
E	50mm Concrete (1:8) blinding bed under bases	138	SM	10,000.00	1,380,000.00		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | Ext wrks priced

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
F	Plain in-situ concrete (grade 15) in trench foundations	47	CM	25,000.00	1,175,000.00		
	In-situ reinforced concrete (Grade 20)				0		
G	Column bases	32	CM	30,000.00	960,000.00		
H	Columns	27	CM	30,000.00	810,000.00		
	Formwork				0		
J	Sides of bases	141	SM	1,250.00	176,250.00		
K	Sides of columns	469	SM	1,250.00	586,250.00		
	External Works Page 5/2 to Collection				7,021,100.00		
	Fencing (contd)				0		
A	16mm Diameter high tensile reinforcement	3546	Kg	1,200.00	4,255,200.00		
B	12mm Diameter high tensile reinforcement	2536	Kg	1,200.00	3,043,200.00		
C	10mm Diameter mild steel links	1550	Kg	1,200.00	1,860,000.00		
	Precast concrete (Grade 20) bedded in cement mortar and finished fair alll round				0		
D	50 x 300mm wide Saddle back coping throated both sides	299	M	2,500.00	747,500.00		
E	Capping size 300 x300 x 100mm thick overall weathered and throated	170	Nr	5,000.00	850,000.00		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | Ext wrks priced

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
F	230mm Hollow blockwalling in cement mortar	897	SM	3,500.00	3,139,500.00		
G	Smooth rendering on walls externally in cement mortar as described	1420	SM	750.00	1,065,000.00		
H	Prepare and prime and apply texcote or other approved textured	1420	SM	650.00	923,000.00		
	paint on rendered walls				0		
J	Provide a sum for Wrought iron fence grilles to be expended as directed				5,000,000.00		
K	Provide a sum for Gates(2Nr) to be expended as directed				1,000,000.00		
L	Provide a Sum for Gate House to be expended as directed				7,000,000.00		
M	Provide a Sum for site drainage to be expended as directed				5,000,000.00		
N	Provide a Sum for soil drainage to be expended as directed				20,000,000.00		
	External Works Page 5/3 to Collection				53,883,400.00		
A	Provide a Sum for Generator House to be expended as directed				5,000,000.00		
B	Provide a Sum for Borehole and Water Treatment to be expended as directed				8,000,000.00		
C	Provide a Sum for Water Storage and Distribution to be expended as directed				10,000,000.00		
D	Provide a Sum for Electricity Supply and Distribution to be expended as directed				20,000,000.00		
	External Works Page 5/4 to Collection				43,000,000.00		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | Ext wrks priced

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	BILL Nr 5 - ETERNAL WORKS						
	Collection						
	Page 5/1				19,574,000.00		
	Page 5/2				7,021,100.00		
	Page 5/3				53,883,400.00		
	Page 5/4				43,000,000.00		
	BILL Nr 5 - EXTERNAL WORKS Page 5/5				123,478,500.00		
	TO MAIN SUMMARY						

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | Summary

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	DEVELOPMENT FOR MR CLETUS UJAH						
	MAIN SUMMARY						
	BILL Nr 1 - CONDITIONS OF CONTRACT,						
	PRELIMINARIES & SPECIFICATIONS				3,000,000.00		
	BILL Nr 2 - 5 UNIT TERRACE BLOCK B				23,150,000.00		Unavailable
	BILL Nr 3 - EXTERRNAL WORKS				123,478,500.00		
	BILL Nr 3 - 4 UNIT TERRACE BLOCK A				Unavailable		
	BILL Nr 3 - 4 UNIT TERRACE BLOCK C				Unavailable		
	BILL Nr 4 - 2 UNIT TERRACE BLOCK D				Unavailable		
	BILL Nr 5 - EXTERNAL WORKS				Unavailable		Unavailable
	CONTINGENCIES						
	Provide a sum for Contingencies to be expended as directed				8,000,000.00		8,000,000.00
					157,628,500.00		
	Add VAT at 20%				31,525,700.00		
	TOTAL CARRIED TO FORM OF TENDER				189,154,200.00		

SAMPLE

AURUM PROJECT CONTROLS

Sample Bill of Quantities | Summary

SAMPLE • FOR ILLUSTRATION ONLY. Original descriptions, quantities, rates and amounts retained from the supplied workbook. Currency: pounds sterling (£).

Unavailable = a broken source formula. Source totals are preserved as supplied. CM = cubic metres; SM = square metres.

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
	Signature of Employer						
	Signature of Contractor						
	Completion period **weeks**						
	MS/1						

SAMPLE