Bill 1 • Access

SAMPLE • Costed housing refurbishment basket • GBP • Revision 02

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
1.01	Facade scaffolding; six-week hire	50	m²	51.31	2,565.50	35.00	1,750.00
1.02	Tower scaffolding; maximum 10m	2	nr	996.70	1,993.40	250.00	500.00
	Carried to summary				**4,558.90**		**2,250.00**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Bill 2 • Building fabric

SAMPLE • Costed housing refurbishment basket • GBP • Revision 02

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
2.01	Render renewal with existing removal	200	m²	132.89	26,578.00	38.00	7,600.00
2.02	Mechanical repointing with existing removal	100	m²	57.14	5,714.00	38.00	3,800.00
2.03	15mm exterior plywood roof decking	50	m²	58.45	2,922.50	53.33	2,666.50
2.04	200mm mineral-wool roof insulation	25	m²	26.58	664.50	27.50	687.50
	Carried to summary				**35,879.00**		**14,754.00**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Bill 3 • Renewals

SAMPLE • Costed housing refurbishment basket • GBP • Revision 02

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
3.01	Kitchen renewal; six units maximum	10	nr	7,020.84	70,208.40	4,920.00	49,200.00
3.02	WC renewal with hand basin	5	nr	1,888.20	9,441.00	590.00	2,950.00
	Carried to summary				**79,649.40**		**52,150.00**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Bill 4 • Electrical

SAMPLE • Costed housing refurbishment basket • GBP • Revision 02

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
4.01	Additional double socket with box	10	nr	76.11	761.10	105.00	1,050.00
4.02	Additional light switch with box	10	nr	16.49	164.90	24.00	240.00
4.03	Additional smoke detector	20	nr	164.91	3,298.20	82.04	1,640.80
4.04	Occupied-property electrical testing after works	20	nr	164.91	3,298.20	200.00	4,000.00
	Carried to summary				**7,522.40**		**6,930.80**

Quantity and price references are listed in the source register. Section totals reconcile with the main summary.

SAMPLE

Main summary

SAMPLE • Costed housing refurbishment basket • GBP • Revision 02

Item	Description	Qty	Unit	Rate (£)	Amount (£)	Alt. rate (£)	Alt. amount (£)
1	Access				4,558.90		2,250.00
2	Building fabric				35,879.00		14,754.00
3	Renewals				79,649.40		52,150.00
4	Electrical				7,522.40		6,930.80
	Total of selected works				**127,609.70**		**76,084.80**

SAMPLE

The two totals are separate price comparisons; they must not be added together. Only the selected work basket is totalled. VAT is not calculated in this example.

Basis and source register

SAMPLE • Costed housing refurbishment basket • GBP • Revision 02

What this sample demonstrates

A complete priced basket with itemised quantities, two source rate sets, trade totals and a reconciled summary. This is a published evaluation example, not a completed client project or a live quotation.

Pricing and quantity basis

Evaluation quantities come from the source schedules. Rates are rounded to pence before multiplication. Each amount equals quantity × rate; totals sum the displayed amounts. Reference prices are historical and have not been escalated to current market levels.

S1 • Published pricing schedule

https://www.royalgreenwich.gov.uk/download/downloads/id/6245/united_living_-_pricing_schedules.xlsx

S2 • Published pricing schedule

https://www.royalgreenwich.gov.uk/download/downloads/id/6246/axis_-_pricing_schedules.xlsx

Retrieved 2026-10-10. The Excel companion contains the full cell-reference register and calculation formulas. The council's framework specifications govern the original rates; this excerpt does not reproduce those specifications.

Before using a BOQ for a real tender

Replace evaluation quantities with measured project quantities; confirm scope, access, specifications, taxes and current prices. Do not add separate preliminaries or overheads without checking what is included in the agreed rates.

SAMPLE